

**Friday 6, 2024**

**Library 21c Water Main Reroute  
RFP #490-24-03-21C**

**Addendum # 1**

The RFP Schedule has been extended at this time:

RFP released ..... Monday August 19  
Mandatory Pre-bid Conference and site walk ..... Monday, August 26 at 9 am  
Deadline for final questions ..... Friday, August 30 at 2 pm  
Deadline to return answered questions ..... Friday, September 6  
Proposals due ..... Tuesday, September 20 at 2 pm  
Board Review and Decision ..... Wednesday, October 16 at 5 pm  
Award Notification ..... on or before Friday, October 18

**Questions:**

1. There were questions regarding the feasibility of doing the boring add alt due to the slope of the hill.
  - a. Directional boring is an acceptable construction means and methods for this location.
2. Was it discovered where the connection was regarding the plans. Was it verified against the plans.
  - a. The contractor will need to pothole and field verify both connection points.
3. The drawings list 90-degree bends, do you want 90 or (2) 45s? Contractors haven't been installing 90s bends for a few years.
  - a. Proposing 45-degree bends are acceptable in lieu of 90-degree bends.
4. In the scope of work, it says to leave the joints open for pressure testing. Do we want that?
  - a. Pressure testing as recommended is acceptable.
5. What location do engineers want to do the backflow and hydrostatic testing?
  - a. The testing can be done near the connection points.
6. Bid bonds were not listed in the RFP. Does this project require them?
  - a. No, they are not required for this project.
7. Will the road be closed?
  - a. Yes, the side service road will be closed while construction is ongoing.
8. Can we price using weekends to not close the road? Are there deliveries on the weekend?
  - a. No need to submit the price for weekend work since the road will be closed for this project.